

- 1030. Juyal, G.P. and Gupta, R.K. 1985.** Construction of LDPE film lined '*Tankas*' in hills-A case study. *Indian J. Soil Conserv.*, 13(1):10-13.

Low cost L.D.P.E. film lined '*tankas*' (tanks) were tried at the Operational Research Project on watershed management at Fakot on farmer's fields. The cost of L.D.P.E. lined '*tankas*' has been found to be less than half of cement masonry ones for one cu m water stored per year for the expected life period. An attempt has been made in this paper to highlight the construction procedure for L.D.P.E. '*tankas*' in the hilly regions.